

Addendum

No. FIVE Date: 10.14.20

Project:

**ADDITION TO SARALAND EARLY EDUCATION CENTER
FOR THE
SARALAND CITY BOARD OF EDUCATION**

**MCKEE PROJECT NO. 2020-108
ALABAMA DEPARTMENT OF CONSTRUCTION MANAGEMENT NO. 2020271**

The following changes and/or substitutions to the plans and specifications are hereby made a part of same and are incorporated in full force as part of the contract.

Bidders shall acknowledge receipt of this Addendum in writing on his Proposal Form.

A5.1 GENERAL MODIFICATIONS:

A. None:

A5.2 SPECIFICATION MODIFICATIONS:

A. The following manufactures are hereby approved subject to the plans and specifications:

SECTION 010100 – MARKER BOARDS AND TACK BOARDS

AJW Architectural Products

SECTION 010160 – TOILET PARTITIONS

American Standard Phenolic

A5.3 DRAWING MODIFICATIONS:

A. None.

A5.4 CLARIFICATIONS:

A. See the following responses to RFI questions received from Contractor's

Question 1: Specification section 9510 calls for a shadow edge molding but the ceiling tile is specified as square edge. Please confirm if a shadow edge is required.

Answer: Shadow edge not required.

Question 2: Drawings call for 5/8" gypsum bd. on the underside of the trusses but the specifications call for 1/2" Please confirm which is required.

Answer: 1/2" is acceptable and minimum thickness.

Question 3: Is a cable tray required for low voltage or are J-hooks acceptable in place of cable tray?

Answer: Provide J-hooks as shown on detail sheet E4.1.

Question 4: Specs call for interior walls to be 22 gauge/27 mil studs, exterior to be 18 ga
Plans call for a 33 mill stud, with 2" flange.

Answer: Provide studs as indicted on structural drawings.

END OF ADDENDUM