

RMT Corporation Assembly Line Tooling....




Project: Stud Assembly Station

Notes: Station used to assembly stud to molded housings using an electric nut driver and controller. Lower shelf provided for storage area. Electrical plug and casters make the station mobile.



Project: HVAC Assembly Pallet

Notes: Pallet used to build Right Hand and Left Hand HVAC Units. Toolless design allows pallet changesover from a Right Hand part to a Left Hand part in seconds.



Project: End Of Line Test Station / Customer Interface Gage

Notes: Tool test part, verifies correct assembly and gages interface with customers part.



Project: HVAC Assembly Cart

Notes: Cart has a horizontal axis of rotation for HVAC assembling. Lock is foot pedal and cable driven for ease of changing from assembly position to position. A shelf type sub assembly station slides in and out.

[back to services](#)