# *In-Situ* Testing of Gas Orifice Meters


By: Ron Beaty, PE David Simpson, MSME both of Amoco Production Co.

#### Overview

- Why do we do *in-situ* testing
- ▼ Test Equipment
- Design Considerations
- ▼ Summary

# Elements of a Differential Producer

- Primary Element--mostly steel; subjected to pressure, temperature, and flow velocity, but no electronics
- Sensing Element--electronics and exotic metals; subjected to pressure and temperature, but not flow; generates electronic signals or pen movements.
- Recording Element--Electronics or pen & ink; only sees electronic signals or pen movements
- Differential Producers are Inferential Devices
  - Assuming all conditions match reference conditions you can use Bernoulli's Equation to infer a flow rate from a differential pressure across a known restriction



### Measurement System Accuracy

- Each element of a measurement system is:
  - manufactured to close tolerances
  - inspected by the manufacturer and purchaser
  - installed to precise specifications
- After all that, what can still be wrong?

#### What can be wrong with a new installation?

- ▼ Flow profile
- Backwards plate
- Beta Ratio
- Incorrect station parameters
- Non-rigid mounting

# Flow Profile

- Problem
  - 25% of flow not in center 20% of pipe
  - Error can be low by 5% or more
- How to prevent it
  - Upstream piping
  - Flow Conditioners and/or Straightening vanes
- How to detect it
  - In Situ Testing



# **Backwards Plate**

- ▼ Problem
  - Leading edge shaped like a venturi
  - Reading can be as much as 26% low
- How to prevent it
  - Attention to details
- How to detect it
  - In Situ testing

# Beta Ratio

- Problem:
  - Uncertainty in gas measurement is controlled to a large extent by beta ratio
    - » Less than 0.3, uncertainty is a function of edge sharpness and concentricity
    - » Greater than about 0.62, it increases very quickly
  - Combined error can be 7%
- How do you prevent it
  - Proper station design
- How do you detect how "uncertainty" equates to "error"
  - In Situ Testing

#### Incorrect station parameters

- Problem
  - Any of the parameters from gas analysis to Tube ID will affect the conversion of dP, P, and T to flow rate
  - Combined error can be over 10%
- What can you do to prevent errors
  - Double check original input (two people)
- What can you do to detect errors
  - Verify all parameters each calibration
  - In Situ Testing

# Non-Rigid Mounting

- Problem
  - The gas does work (reducing dP)
  - up to 15% error
- How to prevent
  - Independent braces
  - Use hold-down bolts
- How to detect
  - Inspection after installation
  - In-Situ testing



#### Installation Verification

- To insure that a new station meets its potential:
  - Install all the parts at their final location
  - Use "normal" gas at "normal" temperature and pressure
  - Design a test manifold that ensures that all gas goes through the test skid after the new station
  - Use a certified test skid

#### When to Test

- As part of station commissioning process
- Regularly on very large volume stations
- Regularly on particularly erosive/corrosive or dirty applications
- When routine plate inspections point to a problem

#### Test Equipment

- Uncertainty
- Calibrated Differential Producer
- Proportional devices with provers
  - Turbine meters
  - Vortex-shedding meters
- Inferential vs. Proportional devices
- Calibration methods

#### Uncertainty


- Uncertainty means "you don't know"
- No conclusions can be drawn from data beyond the uncertainty range, for example:
  - $-\,$  If a calibration device is stated to be  $\pm 0.5\%$
  - Your tested device is off by 0.6%
  - Actual results are 0.1-1.1% and the meter has a bias high
- Consequently:
  - a calibration device can only certify a calibrated device to within twice its uncertainty (i.e., a 0.25% device must be used to calibrate a 0.5% device)
  - Midpoint of a confidence range must fall within the dead-zone around zero (i.e., the center of a 90% confidence range from a 0.5% skid must be in the range -0.5-0.5%)



- As long as:
  - The test manifold has positive isolation between inlet and outlet
  - Sensing elements on test skid are calibrated before every test
  - Orifice plates on test skid are inspected before and after every test
  - Tube on test skid is inspected quarterly
  - Recording elements are verified against a calculation standard frequently
  - The skid is certified against a primary standard annually to be within  $\pm 0.5\%$
- A properly designed Differential Producer Skid can be used to certify a station is ±1.0%


#### **Proportional Devices**

- All have some moving part that is proportional to mass flow rate (motion can be gross like a turbine rotor or microscopic like the vibration frequency of a vortex)
- They are all prone to:
  - Foul in dirty fluid (20 mils of paraffin on a turbine blade caused the reading to be 2% low in one test against a primary standard)
  - Have bearing or vibration-sensor wear that is not obvious on recording element
- A Proportional Skid must be calibrated against a primary standard before and after each station test



## Calibration Methods

- Piston Prover
- Sonic nozzle
- Primary standards not discussed in this paper:
  - Weigh tanks
  - High pressure Bell Prover



## Piston Prover Design Considerations

- Piston run times related to flow by:
  - Precise displacement volume
  - Exact duration of travel between detector switches
  - Exact count of piston round trips
- Obstacles to use in gas
  - No U.S. standards exist for piston provers in compressible flow (some European countries have adopted procedures and ISO is evaluating)
  - Gas pressure must increase to overcome piston inertia
  - Fairly small volume capacity
- Techniques to overcome obstacles
  - New correlations based on equations of state
  - Bi-directional pistons
  - Fast-acting, electronically operated diverter valves
  - Acceleration/deceleration regions before/after measured volume
  - Use Piston to prove turbine and turbine to prove installed station

# Sonic Nozzle

- Under most conditions, a compressible fluid is limited to speeds less than or equal to the speed of sound
- Sonic (or Critical Flow) nozzles use a substantial pressure drop to force the gas to the speed of sound
  - With an open-ended pipe sonic velocity is reached when downstream pressure (psia) is less than 1/2 upstream pressure
  - Properly designed convergent/divergent nozzles can reduce this to about 20% pressure drop
- With careful measurement of upstream pressure, temperature, and gas composition; very accurate (about ±0.25%) mass flow measurement is possible so volumes can be accurately determined

## Sonic Nozzle Limitations

- They require a large differential pressure, so:
  - It can be difficult to get the gas back into the line
  - If hydrocarbon gas is discharged to atmosphere, care must be taken to avoid an explosive atmosphere
  - Liquids can drop out of gas
  - Temperature drop can cause hydrates to freeze
- They are not effective in multi-phase flow
- Calculations require careful evaluation of:
  - Atmospheric pressure
  - Upstream temperature and pressure
  - Density
  - Compressibility

# Sonic Nozzle Use in In-Situ Testing


- Considerations
  - Use dry air or non-flammable gas as test fluid
  - Ensure that operating personnel are careful, competent, and observant
  - Verify that atmospheric pressure and gas composition are the same in EFM unit as in test-facility computer
  - Verify that EFM unit uses the same Temp and Pressure base as the test facility
  - Verify that EFM unit uses the same compressibility calculation as test facility
- With proper diligence, a sonic nozzle can be used to certify that the differential producers on a test skid are accurate to ±0.5% of volumetric flow rate


# Test Skid Design Considerations

- Flow conditioning
- Capacity and Rangeability
- Operating pressures and temperatures
- Flexibility
- Data Capture
- Transportability




- Any device used on a test skid will be sensitive to flow profile problems
- Confined-space piping on test skid will contribute to poor flow profiles
- Swirl and asymmetry cause flow-rate errors that are related to compressibility and density
- Flow conditioners with straightening vanes are required to get repeatable results that can be transferred from one type of gas to another







# **Operating Pressures & Temperatures**

- The test skid (excluding hoses) should be designed to handle 150% of design pressure on highest design-pressure station in the operation
- Increase hydrostatic test pressure to compensate for the lowest ambient temperature expected
- Hoses should be:
  - Designed for most-likely pressures and temperatures
  - Labeled with MAOP
  - Tested to 150% of MAOP annually (hold test for 24 hours)



- The test skid should be able to:
  - Use one meter to evaluate one stream
  - Use some combination of skid meters in parallel for larger streams
  - Simultaneously evaluate multiple flow streams
  - Re-measure a given stream multiple times
- Possible reasons to re-measure
  - Compare one meter to another to quickly evaluate "calibration"
  - Evaluate impact of damaged plates
- Streams must be positively isolated from each other
  - Double-Block-and-Bleed valves
  - Spectacle blinds





## Data Analysis

- At least 30 time periods must be used, any number greater than 30 is acceptable
- It is better to use cumulative gas for each time period than to use flow rates
- Calculate:

 $Error = \frac{\sum Skid Volume - \sum Station Volume}{\sum Skid Volume} \times 100$ 

- Total error should be less than 1%
- Error for individual time periods should be computed and checked for:
  - » Standard deviation of errors
  - » Mean error
  - $\,$  > Count of periods above and below zero (worse than 60-40% distribution indicates a bias when n>30)

90%Confidence =  $\frac{1.65 \times \text{Standard Deviation}}{\sqrt{\text{Sample Count}}} = \text{CONFIDENCE}(0.10, \text{Std Dev}, n)$ 

Data A	Analysis Exa	ample		
		- Acceptable Range	Meter 1	Meter 2
	Total Error	-1% to 1%	-0.88%	-0.32%
	Mean Error		-0.99%	-0.07%
	Std Deviation		0.58%	0.42%
	90% confidence	-1% to 1%	-1.10% to -0.88%	-0.15% to 0.0%
	Count < 0	32-48	75	44
	Count > 0 Conclusion	32-48	5 Bias low	36 Accurate Meas
	Conclusion		Dius iow	recurate meas
▼ ]	Notes:			
	<ul> <li>Total error and means</li> <li>conclusions can be</li> </ul>	an error values -0.5 drawn about where		
				•
	<ul> <li>Midpoint of 90% c</li> </ul>	onfidence range mu	st fall between -0.	5 to 0.5% on passing test
	<ul> <li>Rule of thumb court</li> </ul>	nt range		
	» 30 <n<100 ==""></n<100>	acceptable range $= 0.4$	In to 0.6n	

## Transportability

- Considerations
  - Weight
  - Width (limited to about 8-feet)
  - Fitting all piping/equipment onto skid
- Non-negotiable items
  - Isolation between streams must be positive (either block and bleed or spectacle blinds)
  - Differential producers must have dual-chamber fittings
  - Flow profile-isolating conditioner must be installed upstream of each station

#### Transportability Options

- Truck Mounting
  - Larger weight-carrying capacity
  - Considerable flexibility in skid size
  - Leveling can be tricky
  - Transportation for driver can be a problem after hook-up
  - Bed height can be a problem with operations personnel
- Trailer mounting
  - Many weight/size compromises needed
  - Axles and tongue (or 5th wheel) need to be matched to weight
  - Less expensive than truck-mounted
- Cargo
  - Least expensive
  - Least convenient for moving

#### Summary

- *In-Situ* testing is both necessary and practical
- It ensures
  - The measurement system works together
  - Large stations continue to work
  - Stations in dirty/corrosive/erosive streams continue to work
- Skid certification:
  - Proportional skids should have a built-in prover
  - Differential-producer skids should be calibrated periodically
- The skid must be designed to
  - be transported, leveled, and connected to the process gas
  - allow a wide variety of flows
  - work with expected fluid pressures, temperatures, and fluid qualities
  - capture data consistent with installed equipment